

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 173-42279.00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 6-2-64.

Well Operator: W.D. Short (Owner / Company Name) KCC License #: 6679 (Operator's)

Address: PO Box 729 City: Oxford

State: Kansas Zip Code: 67119 Contact Phone: (620) 455 - 3576

Lease: O.S.A. Well #: 28 Sec. 22 Twp. 29 S. R. 1 East West

SE - NW - NE Spot Location / QQQQ County: Sedgwick

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 341' Cemented with: 300 Sacks

Production Casing Size: 5 1/2" Set at: 3724' Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: Open Hole 3723'-41'

Elevation: 1281' (G.L. / K.B.) T.D.: 3741' PBDT: _____ Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per KCC Orders

RECEIVED

JUL 14 2004

KCC WICHITA

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Do not have ACO-1 in permanent file but I would believe it was filed

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Don Short

Phone: (620) 455 - 3576

Address: PO Box 729 102 S. River Road City / State: Oxford, KS 67119

Plugging Contractor: Braden Well Plugging Company (Company Name) KCC License #: 32475 (Contractor's)

Address: PO Box 282 Burden, KS 67019 Phone: (620) 438 - 2856

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7-12-04 Authorized Operator / Agent: W.D. Short (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DIX #4

Casing Record: Company: Aylward Drilling Company Location: SE NW NE
 8 5/8" - 341' Contractor: Aylward Drilling Company Sec. 22-29-1W
 5 1/2" - 3724' Commenced: June 2, 1964 Sedgwick County, Kansas
 Completed: June 11, 1964 Elev. 1281 DF, 1284 RB

OK

	<u>From</u>	<u>To</u>	<u>Remarks</u>	
Shale	0	30	Set 8 5/8" surface pipe @ 341' w/300 sacks.	
Sand	30	70		
Lime & Shale	70	270	Geological Tops:	
Lime	270	560		
Lime & Shale	560	2205		
Shale	2205	2465		Stalnaker 2464
Shale & Sand	2465	2580		Kansas City 2788
Lime & Shale	2580	2973		Base Kansas City 2999
Lime	2973	3205		Mississippi 3357
Lime & Shale	3205	3300		Kinderhook 3662
Lime	3300	3665		Simpson 3723
Lime & Shale	3665	3720		
Sand	3720	3741 T.D.		

D.S.T. 3720-41 Open 1'40"
 Rec. 1125' oil & 15' mud
 IBHP 1135#/30" - FBHP 1153#/30"
 FP 27#-370#

Set 5 1/2" casing @ 3724' w/75 sacks.

15-173-42 279-00-00

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

William Jessup

Subscribed and sworn to before me this 6th day of August, 1964

Joseph A. Hess
Joseph A. Hess - Notary Public

My commission expires May 14, 1968

RECEIVED
JUL 14 2004
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Short, W.D. d/b/a Short, W. D. Oil Co.
PO Box 1
Oxford, KS 67119

July 16, 2004

Re: O.S.A. #28
API 15-173-42279-00-00
SEWNNE 22-29S-1W, 990 FNL 1650 FEL
SEDGWICK COUNTY, KANSAS

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231