

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-153-20, 462 00-00

SE, Sec. 36, T 2 S, R 31 WE

2310 feet from N(S) section line

2310 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6063

Lease Name Mechenstock Well # 1

Operator: Sedessa Corporation  
Name & Address 1125-17th, Suite 2220  
Denver, Co. 80202

County Rowline

Well Total Depth 4190 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 300'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Dalg., Inc. License Number 179

Address 801 Union Center, Wichita, Ks. 67202

Company to plug at: Hour: 11:00 AM Day: 24 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Harold Maley

(company name) Abercrombie Dalg., Inc. (phone) 316-262-1841

were: Order out 180 sacks. 50 posmix - 6% cel. - 3% cal. ll. + 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 2750' w/ 20 sacks,

2nd plug C 1500' w/ 100 sacks, 3rd plug C 350' w/ 40 sacks, 4th plug -

Solid bridge of hulls + plug C 40' w/ 10 sacks.

Circulate 10 sacks in rat hole.

Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:00 PM Day: 24 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 300' SP. cas. w/ 235 sacks common - 2% cel. - 3% cal. ll.

Ordered 180 sacks 50 posmix - 6% cel. - 3% cal. ll. + 8 5/8" plug. Spot w/

drill stem w/ heavy mud between all plugs. 1st plug C 2750' w/ 20 sacks,

2nd plug C 1500' w/ 100 sacks, 3rd plug C 350' w/ 40 sacks, 4th plug -

Solid bridge of hulls + plug C 40' w/ 10 sacks.

Circulated 10 sacks in rat hole.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

NOV 08 1982 11-8-82

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 12-6-82  
INV. NO. 1773-W

Signed [Signature] (TECHNICIAN)

FORM CP-2/3  
Rev. 9-82