

4-060762

10-19

API Number: 15-153-20,807-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NW SE NW /4 SEC. 08, 02 S, 31 W  
3630 feet from S section line  
3630 feet from E section line

Operator license# 5131

Lease: Solko "A" Well # 1

Operator: Thunderbird Drilling, Inc.

County: Rawlins 127.40

Address: P.O. Box 780407  
Wichita, Kansas 67278

Well total depth 3920 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 309 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 19 Month: October Year: 1995

Plugging proposal received from: Tony Martin

Company: Abercrombie RTD, Inc. Phone: 316-262-1841

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 4:45 A.M. Day: 19 Month: October Year: 1995

Actual plugging report:

- 1st. Plug at 2500' w/25 sxs. - Anhydrite 2471' - 2506'.
- 2nd. Plug at 1875' w/100 sxs. - Dakota 1562' - 1862'.
- 3rd. Plug at 360' w/40 sxs. - Surface pipe to 309'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1995

11-13-95  
CONSERVATION DIVISION

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: 2712 GL

I did [ ] did not [ X ] observe the plugging.

DATE 11-15-95  
INV. NO. 44014

(agent)  
Form CP-2/3