

4-032176

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

9-17

API Number: 15-153 20802-00-00
130'S.of
S2 NW NW /4 SEC. 08 , 02 , 31 W
4290 feet from S section line
4620 feet from E section line

Operator license# 5131 Lease: Solko Well # B-1

Operator: Thunderbird Drilling, Inc. County: Rawlins

Address: P.O. Box 780407 Well total depth 3920 127.40 feet
Wichita, Kansas 67278-0407 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 316 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# -

Address: Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 17 Month: September Year: 1996

Plugging proposal received from: Jim Ray

Company: Mike's Testing & Salvage Phone: -

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order sand and common cement.

RECEIVED
KANSAS CORP COM
1996 OCT -2 A 12:5

10-2-96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30 A.M., Day: 17, Month: September, Year: 1996

Actual plugging report: 8 5/8" set at 316' cwc. 4 1/2" set at 3915' with 150 sxs. PBTD 3890'. Prod. perf. 3818' - 3822'. TOC 3018'. Sanded back to 3770' w/4 sxs common cement on sand with bailer. Recovered 2390' of 4 1/2" casing. Mixed and pumped 135 sxs to 2390'. Pulled casing to 325' - circulated with 60 sxs cement blend. Pulled 4 1/2" casing - topped off with 30 sxs. Used total 225 sxs cement blend with 500# hulls mixed in. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow (agent)

PO

Form CP-2/3

INVOICED
DATE 10-3-96
INV. NO. 46654