

6 010528

MAY 29 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,686-00-00
SW, SEC. 6, T. 2 S, R. 31 W
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6467

Lease Name Bockwinkle Well # 1

Operator: West Ks Oil Corp.
Name & Address Box 77
Selden, Ks.

County Rawlins 145.05
Well Total Depth 4463 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger License Number 5302

Address Wichita, Ks.

Company to plug at: Hour: _____ Day: 29 Month: 5 Year: 19 87

Plugging proposal received from Bill Airs

(company name) Red Tiger (phone) _____

were: Order 215 sx cement 60/40 pozmix 6 % gel,
Heavy mud between all plugs

Pump cement down drill pipe

Elev 2790, anhydrite 2551.86 Arbuckle 4305 Dakota 1150
1640 = 1940

Plugging Proposal Received by Dale F. Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:PM Day: 29 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT

25 sx at 4305
25 sx at 2570
100 sx at 1940
40 sx at 320
10 sx at 40

RECEIVED
STATE CORPORATION COMMISSION
6-5-87
JUN 5 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: 15 sx in Rat Hole Cementing Co. Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

(did, did not) observe this plugging.

DATE 6-5-87

Signed Dale F. Balthazor (TECHNICIAN)

INV. NO. 17179

5-29

170 days

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 5 21 87 month day year

API Number 15- 153-20,686-00-00

OPERATOR: License # 6467 Name WEST KANSAS OIL CORPORATION Address RR 1, Box 77 City/State/Zip Selden, Kansas 67757 Contact Person Charles Young Phone 913-475-2766

SW SW Sec. 6 Twp. 2 S, Rg. 31 East West 660 4620 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302 Name Red Tiger Drilling Co. City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 660 feet County Rawlins Lease Name Bockwinkel Well # 1

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Ground surface elevation feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 120 Depth to bottom of usable water 250 Surface pipe by Alternate: 1 X 2

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

Surface pipe planned to be set 260 Conductor pipe required N/A Projected Total Depth 4300 Formation Granite Wash

I certify that well will comply with K.S.A. 55-101, et seq., plus existing zoning hole to KCC specifications.

Date 5/19/87 Signature of Operator or Agent Title OWNER

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. 1 This Authorization Expires 11-19-87 Approved By 5-19-87

Bill Bryan

5-21-87 - Water Hauled

J.P.H.

SW SW Sec. 6 Twp. 21 S, Rg. 31W East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Anhydrite feet depth with 25 sxs of 60-40 poz., 6% gel 2nd plug @ Base of Dakota feet depth with 100 sxs of 3rd plug @ 310 feet depth with 40 sxs of 4th plug @ 40 feet depth with 10 & wiper plug sxs of 5th plug @ feet depth with sxs of (2) Rathole with 15 sxs (b) Mousehole with sxs

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging. In Addition: Call district office after well is either plugged or production casing is cemented in.

(Call 7 a.m. to 5 p.m. workdays)

District office use only:

API #15 153-20,686 Surface casing of feet set with sxs at hours 19 Alternate 1 or 2 surface pipe was used. Alternate 2 cementing was completed @ ft. depth with sxs of 19 Hole plugged 19, agent

Received KCC District #6

MAY 20 1987 RECEIVED STATE CORPORATION COMMISSION Hays, KS

JUN 5 1987 6-5-87 CONSERVATION DIVISION Wichita, Kansas

Form C-1 12/85