

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21201-00-02  
Spot: NWSW Sec/Twnshp/Rge: 18-30S-33W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: ANTON Well #: 1-1218  
County: HASKELL Total Vertical Depth: 6600 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

MSCC Size: feet: 4851 WITH 230 SX CMT  
PROD Size: 4.5 feet: 5656 WITH 80 SX CMT  
SURF Size: 8.625 feet: 1650 WITH 700 SX CMT

*\$ 214<sup>50</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2004 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4300' & 4 SX CMT. PLUG AT 1680' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/02/2004 3:15 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5606'. DV TOOL @ 4851' WITH 230 SX CMT. CMT TOP @ 3830'. SAND TO 4300' WITH 4 SX CMT ON TOP. 1ST PLUG PULL CASING TO 1680'. SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 600' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5461	5470		
4994	4998		
4394	4401		

RECEIVED  
JUL 12 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1900' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JUL - 7 2004  
KCC Dodge City

Signed

*[Signature]*

(TECHNICIAN)

INVOICED  
DATE 7-13-04  
BILL NO. 2005060054

Form CP 2/3  
*[Signature]*