

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-153-20802-00-00

LEASE NAME Solko

WELL NUMBER B #1

           Ft. from S Section Line

           Ft. from E Section Line

SEC. 8 TWP. 2S RGE. 31W (E) or (W)

COUNTY Rawlins

Date Well Completed           

Plugging Commenced 9-12-96

Plugging Completed 9-17-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P. O. Box 97 Ellinwood, KS 67526

PHONE# (316) 564-2577 OPERATORS LICENSE NO. 5131

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on            (date)

by            (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached?           

Producing Formation            Depth to Top            Bottom            T.D. 3920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	316'	none
				4 1/2	3915'	2480'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from    feet to    feet each s  
Plugged off bottom with sand to 3768' & 4 sks cement. Shot casing at 2880' and 2480'. Came loose at 2480'. Pulled casing up to 2200', mixed 130 sx cement w/500# hulls. Pulled casing to bottom of surface and mixed 60 sx cement. 60/40 pos 10% gel. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 96

*Irene Herzberg*  
Notary Public

9-24-96  
KANSAS CORP COM  
RECEIVED  
My Commission Expires:           

