

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Landmark Resources, Inc. Address: 1616 S. Voss Rd., Ste. 150, Houston, TX 77057 Phone: (713) 243-8551 Operator License #: 6113 Type of Well: Input Oil (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) Docket #: (If SWD or ENHR) The plugging proposal was approved on: 3/1/04 by: Darrel Dipmon (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [ ] No Producing Formation(s): List All (If needed attach another sheet) Kansas City Depth to Top: 3626 Bottom: 3850 T.D. 3868

API Number: 15 - Spud 5/25/04 179-05583-0002 Lease Name: Adell Lansing KC KCC BEM Well Number: 304 7-16-04 Spot Location (QQQQ): NE - SW - NE - 3630 Feet from [ ] North / [X] South Section Line 1650 Feet from [X] East / [ ] West Section Line Sec. 11 Twp. 6 S. R. 27 [ ] East [X] West County: Sheridan Date Well Completed: 3-2-04 KCC Plugging Commenced: 5/28/04 BEM 7-16-04 Plugging Completed: 3/3/04

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Kansas City, Oil and Water, 0, 240, 10 3/4, 240, 0. Row 2: Kansas City, Oil and Water, 0, 3866, 6", 3866, 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf Anhydrite @ 2266-68 & Dakota @ 1450-52 & btm of surf csg @ 375-377. Run tbg to 3565'. Mix & pump 420 sx 60-40 poz w/ 10% gel and 1000# hulls. Cement to surface (0-3565'). POH w/ tbg. Pump 20 sx 60-40 poz down 6".

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606 Address: 250 N. Water St., Ste. 300, Wichita, KS 67202

RECEIVED JUN 14 2004 KCC WICHITA

Name of Party Responsible for Plugging Fees: Landmark Resources, Inc. State of Kansas County, Sedgwick, ss.

Charles Schmidt (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Charles E. Schmidt (Address) 1321 W. 93rd St. North, Valley Center, KS 67147

SUBSCRIBED and SWORN TO before me this 11th day of June 2004. Notary Public - State of Kansas MARSHA BREITENSTEIN My Commission Expires: September 2007 My Appointment Expires 9-15-07