

KANSAS

X
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20219-00-00

RECEIVED
STATE CORPORATION COMMISSION
11-29-1971
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated, & National Oil Company,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name May Well No. 1

Location CNE-SW Sec. 32 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 4180'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address 905 Century Plaza, Wichita, Kansas License No.

Operation Completed: Hour 11:00 AM Day 21 Month 11 Year 1971

The above well was plugged as follows:

212'---8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1725'.

Circulated hole with heavy mud. Pulled DP to 1950' and displaced 100 Sx. cement thru
DP from 1950' to 1625'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*
Well Plugging Supervisor

DATE 12-1-71

INV. NO. 4905-W