



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

15-039-20066-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of A. L. Abercrombie, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated.

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Berndt Well No. 2

Location: App.-CSW-NE Sec. 35 Twp. 2 Rge. (E)(W) 30

County: Decatur Total Depth 4085 Oil Well

Gas Well Input Well AWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

256'--7" OD Surface casing, cement circulated with 75 Sx. (6 1/2" Hole).
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1650' and displace 60 Sx.
cement thru DP. Pull DP to 275' and displace 15 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent