



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
11-29-1971
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

15-039-20219-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerry Nestlerode of Chief Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Nestlerode guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc., & National Oil Company,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: May Well No. 1

Location: CNE-SW Sec. 32 Twp. 2 Rge. (E)(W) 30

County: Decatur Total Depth 4180' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nestlerode was instructed to plug the well as follows:

212'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1725'.

Circulate hole with heavy mud. Pull DP to 1950' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent