

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20512-00-01
Spot: CNWNENE Sec/Twnshp/Rge: 36-2S-30W
4950 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: UNG UNIT WSW ETHEL RO Well Number: 1
County: DECATUR Total Vertical Depth: 4030 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 301 260 SX CMT
Production: Size 4.5 feet: 4003 100 SX CMT
Liner: Size feet: 8130.98

Well Type: WSW UIC Docket No: Date/Time to Plug: 08/28/2001 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-6701

Proposed Plugging Method: Orderd 120 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/28/2001 2:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 301' cwc. 4 1/2" set at 4002' w/CIBP at 3350'.
Squeezed 2270' - 2271' with 100 sxs.
PBTd 2350'. Tools stuck in the hole at 2247'.
Prod.Perfs 2300' - 2328'.
Exempt area.
Squeezed 8 5/8" with 20 sxs cement blend to Max. P.S.I. 300#. Held.
Squeezed 4 1/2" with 100 sxs to Max. P.S.I. 250#. Held.
Plug complete.

RECEIVED
09-11-2001
SEP 11 2001
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS ETHEL ROGERS #3-36. SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

D

Signed Carl Goodrow
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-11-01

INV. NO. 2002060449

SEP 05 2001

MURFIN DRILLING CO

517 UNION CENTER

WICHITA, KS 67202

#3-36 ETHEL ROGERS

36-2-30W
NW NE NE

CONTR COMPANY TOOLS

CTY DECATUR

GEOL

FIELD UNG

E 2773 KB CM 10/24/80 CARD ISSUED

3/12/81

IP P 3.84 BO & 44.16

BWPD, LANS 3773-3792

OA

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

API 15-039-20,512

| LOG | TOPS | DEPTH | DATUM |
|-------|------|-------|-------|
| ANH | | 2520 | + 253 |
| B ANH | | 2552 | + 221 |
| SEV | | 3600 | - 827 |
| TOP | | 3637 | - 864 |
| OREAD | | 3725 | - 952 |
| TOR | | 3770 | - 997 |
| LANS | | 3785 | -1012 |
| BKC | | 3994 | -1221 |
| TD | | 4030 | -1257 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

8-5/8" 30/260sx, 4 1/2" 4003/175sx

DST (1) 3745-3800/30-60-60-60, REC
210' OCM, 120' OCW, SIP 1312-
1270#, FP 74/127#

DST (2) 3800-3822/30-60-60-60, REC
40' M, SIP 116-84#, FP 42/52#

MICT - CO, PF 16/3773-3775 & 32/3788-
3792, AC 500 GAL, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

15-039-20,512