

4-032134

E-25,518

API Number: 15-039-0298-00-01

3-15

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NW NW SW /4 SEC. 36, 02, 30 W  
2310 feet from S section line  
4950 feet from E section line

Operator license# 30606 Lease: UNG Unit Well # 7-1

Operator: Murfin Drilling Company County: Decatur

Address: 250 N. Water - Suite #300  
Wichita, Kansas 67202  
Well total depth 4051 131.65 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 266 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 15 Month: March Year: 1996

Plugging proposal received from: John Turner

Company: Murfin Drilling Company Phone:

Were: Order 275 sxs 60/40 pozmix - 10% gel - 300# hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
3-27-96  
6:27 1996  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 1:15 P.M., Day: 15, Month: March, Year: 1996

Actual plugging report: 8 5/8" set at 266' cwc. 4 1/2" set at 4021'. Prod. Perfs. 3843' - 3876'. Squeezed 4 1/2" with 250 sxs cement blend with 300# hulls miced into Max. P.S.I. 750#. Close in P.S.I. 300#. Squeezed 8 5/8" with 25 sxs cement blend to Max. P.S.I. 300#. Held.

Remarks:  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ ] / did not [ X ] observe the plugging.

INVOICED

DATE MAR 28 1996

INV. NO. 45154

Carl Goodrow  
(agent)

Form CP-2/3