

4-031765

9-16

26  
R

15-039-20064-00-00

API number: 15- - 1968

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SW NW /4 SEC. 36, 02 S, 30 W  
3630 feet from S section line  
4950 feet from E section line

Operator license# 30606

Lease Ung Unit well # 5-1

Operator: Murfin Drilling Company, Inc.

County Decatur /32.11

Address: 250 N. Water  
#300  
Wichita, Kansas 67202

Well total depth 4065 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 224 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton License#    

Address: Oberlin, Kansas

Company to plug at: Hour: P.M. Day: 16 Month: September Year: 92

Plugging proposal received from: John

Company: Murfin Drilling Company, Inc. Phone:    

Were: Order 450 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Hole open to perf.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

Completed: Hour: 2:00P.M., Day: 16, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 224' w/160 sx. cwc. 5 1/2" set @  
4063'w/100 sx. P.B.T.D. 3902'. Perf. 3843' - 3954'. Shot @ 1800' Kiowa.  
Squeezed 5 1/2" with 350 sx. cement blend with 400# hulls mixed in to  
Max. P.S.I. 600#. Close in P.S.I. 200#. Squeezed 8 5/8" w/100 sx.  
cement blend w/100# hulls mixed in to Max. P.S.I. 300#. Close in P.S.I.  
200#. Plug complete.

RECEIVED

STATE CORPORATION COMMISSION

Remarks:

Condition of casing(in hole): GOOD     BAD     Any plug: YES X NO    

Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO    

Plugged through TUBING    , CASING X. Elevation:    

I did [ X ] / did not [     ] observe the plugging.

DATE 10-19-92

INV. NO. 36498

Carl Goodrow

(agent)

Form CP-2/3

10-08-1992  
OCT 8 1992

CONSERVATION DIVISION  
Wichita, Kansas