

6 030670

297-110

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-039-20,297-00-00  
NE, SEC. 35, T. 2 S, R. 30 (W)  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5393  
Operator: AL ABERCROMBIE INC.  
Name & Address 801 UNION CENTER  
WICHITA, KANSAS  
67202

Lease Name BERNOT Well # 3  
County DECATUR 134.23  
Well Total Depth 4130 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 245'

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING License Number 6050  
Address CHASE KANSAS.

Company to plug at: Hour: PM Day: 19 Month: 2 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING. (phone) \_\_\_\_\_

were: 8 5/8" @ 245' w/150sx. 4 1/2" @ 4129' w/150sx. PERF 3883-4032' PBD 4095'  
ORDER SAND & Com. CMT. RECOVER PIPE ORDER 180SX. 60/40 P62.6% GEL  
3% GEL 40 SX. GEL 4 SX. HULLS. 8 5/8" W.P. B-J. TITAN CMT. CO. KARUE WATER.

Plugging Proposal Received by Carl Goodnow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:PM Day: 19 Month: 2 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 3800' SPOT 4 SX. CMT ON SAND W/BAILER  
RECOVERED 1727' OF 4 1/2"

MIX. & Pump Down 8 5/8 3SX. HULLS 10SX. GEL 100SX. CMT. MIX. 1SX. HULLS  
30 SX. GEL 8 5/8 W.P. 80 SX. CMT. MIX. MAX. PST 250' CLOSE IN 250'  
Plug. COMPLETE

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 28 1986  
INV. NO. 12784

RECEIVED  
STATE CORPORATION COMMISSION  
02-28-1986  
FEB 28 1986

Signed Carl Goodnow  
(TECHNICIAN)

12  
2-28-86