

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-039-20064-00-00
 API NUMBER compl 10/68

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Ung Unit
 WELL NUMBER 5-1
3630 Ft. from S Section Line
4950 Ft. from E Section Line
 SEC. 36 TWP. 2 RGE. 30W (E) or (W)
 COUNTY Decatur
 Date Well Completed 10/68
 Plugging Commenced 9/16/92
 Plugging Completed 9/16/92

LEASE OPERATOR Murfin Drilling Co., Inc.
 ADDRESS 250 N. Water, Suite 300
 PHONE# () 267-3241 OPERATORS LICENSE NO. 6033

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
 by _____ (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	224	-
				5 1/2	4063	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Perf @ 1800' w/1 SPF. FL 930' f/s. Hooked up to 8 5/8, pumped 100 sx. 65/35 Poz, 10% gel & 100# hulls. MP 300#. SIP 200#. Hooked up to 5 1/2, pumped 350 sx. same & 400# hulls. MP 600#. SIP 200#. JC 2 p.m. Approved by Carl Goodrow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Co., Inc. License No. 30606
 Address Wichita, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Co., Inc.
 STATE OF Kansas COUNTY OF Sedgwick, ss.


Patrick T. Canaday, Production Supt. (Employee of Operator) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) By: Patrick T. Canaday
 (Address) Colby, KS

SUBSCRIBED AND SWORN TO before me this 13 day of October, 19 92

Kerran Redington
 Kerran Redington Notary Public

My Commission Expires: 2/6/94



15-039-20044-00-00

DRILLERS LOG

No. 1 Rogers

CASING RECORD:	COMPANY:	Solar Oil Company	DESCRIPTION:
8 5/8" @ 224' w/160 sx cement	CONTRACTOR:	Red Tiger Drilling Company	NW SW NW 36-2S-30W Decatur Co., Kansas
5 1/2" @ 4063' w/100 sx cement	COMMENCED:	October 9, 1968	ELEVATION:
TOTAL DEPTH: 4065'	COMPLETED:	October 17, 1968	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale and sand	0	225	
Shale	225	940	
Shale and sand	940	2240	
Shale shells	2240	2332	
Anhydrite (Blaine)	2332	2350	
Shale Shells Red bed	2350	2585	
Anhydrite	2585	2612	
Shale and shells	2612	2750	
Shale	2750	3045	
Shale and lime	3045	3808	
Lime	3808	4065	

3630 FS
4950 FS
RECEIVED
KANSAS CORPORATION COMMISSION
OCT 14 1968
CONSERVATION DIVISION
WICHITA, KS

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 23rd day of October, 1968.

Jean Shollar
Notary Public

My Commission Expires:

5-22-70