


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-039-20066-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Decatur County. Sec. 35 Twp. 2S Rge. (#) 30 (W)
Location as "NE/CNW%SW%" or footage from lines C SW NE
Lease Owner A. L. Abercrombie, Inc.
Lease Name Berndt Well No. 2
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 16, 19 68
Application for plugging filed (verbally) October 15, 19 68
Application for plugging approved " " 19 "
Plugging commenced " " 19 "
Plugging completed October 16, 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4085 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	256'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @1650' with 60 sacks;
Set 2nd plug @275' with 15 sacks;
Set top plug @40' with 7 sacks;
Put 3 sacks in rat hole.
Job completed at 3:30 a.m., October 16, 1968

RECEIVED
STATE CORPORATION COMMISSION
10-18-1968
OCT 18 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
A. L. Abercrombie (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 19 68

My commission expires July 15, 1972

[Signature]
Sue J. Brunck, Notary Public.

CONTRACTOR'S WELL LOG

15-039-20066-00-00

OWNER: A. L. Abercrombie, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 LEASE: BERNDT #2
 LOCATION: C SW NE, Sec. 35-2S-30W
 Decatur County, Kansas
 SPUD DATE: October 9, 1968
 COMPLETION DATE: October 16, 1968
 GEOLOGIST: Jack K. Wharton

0	40	Dirt
40	130	Clay
130	190	Sand
190	2235	Shale
2235	2440	Shale with Gyp
2440	2591	Shale
2591	2623	Anhydrite
2623	2945	Shale
2945	2970	Ft. Riley Lime
2970	3860	Lime and Shale
3860	4085	Lime
	4085	Rotary Total Depth

Drilled 268' of 9" surface hole and set 7", 24# csg. w/75 sx. Sunset cement @256'. Cement circulated. Plug was down 7:00 p.m., 10-9-68. Dry & Abandoned.

FORMATION	SAMPLE TOPS	ELEVATION
Top/Anhydrite	2591 (+ 227)	2818 K. B.
Heebner	3793 (- 975)	2816 D. F.
Toronto	3830 (-1012)	2810 G. L.
Lansing	3843 (-1025)	

RECEIVED
 STATE CORPORATION COMMISSION
 10-18-1968
 OCT 18 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

A. L. Abercrombie, President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the BERNDT #2, C SW NE, Sec. 35-2S-30W, Decatur County, Kansas, as of this 17th day of October, 1968.

ABERCROMBIE DRILLING, INC.

A. L. Abercrombie
 A. L. Abercrombie
 President

Sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, as of the 17th day of October, 1968.

Sue J. Blunck
 Sue J. Blunck
 Notary Public

My Commission Expires:

July 15, 1972