

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20050-00-00

LEASE NAME Berndt #1

WELL NUMBER _____

SPOT LOCATION NE SE NE

SEC. 35 TWP. 2s RGE. 30w (E) or (W) (W)

COUNTY Decatur

Date Well Completed _____

Plugging Commenced 2/12/86

Plugging Completed 2/19/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 801 Union Center, Wichita, Ks. 67202

PHONE # (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4077'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				7"	247'	none
				4 1/2"	4076'	1621'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 4000' & 4 sacks cement. Shot pipe at 2518', 2021', 1621'. Pulled 52 joints of pipe. Plugged well with 4 hulls, 40 gel, & 180 sacks 60/40 poz 6% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of February, 1986

My Commission expires:



STATE CORPORATION COMMISSION Notary Public

FEB 26 1986
02-26-1986
CONSERVATION DIVISION

Form CP-4
Revised 01-84

CONTRACTOR'S WELL LOG

15-039-20050-00-00

OWNER:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
LEASE:	BERNDT #1
LOCATION:	NE SE NE, Sec. 35-2S-30W Decatur County, Kansas
SPUD DATE:	June 19, 1968
GEOLOGIST:	Jack K. Wharton

0	40	Lime
40	200	Rock w/Sand
200	1390	Shale
1390	1862	Sand & Shale
1862	2240	Shale w/Gyp Streaks
2240	2576	Shale
2576	2609	Anhydrite
2609	2755	Shale
2755	3050	Shale w/Sand Streaks & Lime
3050	3873	Lime & Shale
3873	3892	Lime
3892	4077	Lime
	4077	R. T. D.

Drilled 250' of 9" hole & set 7" csg. @247' w/75 sx. Sunset cement.
 Plug was down 6-19-68.
 Set 4½", 10½" csg. @4076' w/150 sx. 50/50 Posmix cement.

SAMPLE FORMATION TOPS			ELEVATION
T/Anhydrite	2576	(+ 236)	2812 K. B.
Heebner	3785	(- 973)	2810 D. F.
Toronto	3819	(-1007)	2804 G. L.
Lansing	3835	(-1023)	

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK) SS

A. L. Abercrombie, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Berndt #1, NE SE NE, Sec. 35-2S-30W, Decatur County, Kansas.

A. L. Abercrombie
 A. L. Abercrombie, President

Sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, as of the 8th day of July, 1968.

Mildred Saxton
 Mildred Saxton, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 24 1986
 CONSERVATION DIVISION
 Wichita, Kansas

