


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decatur County, Sec. 32 Twp. 2S Rge. 30 (XXX) (W)
Location as "NE/CNW%SW%" or footage from lines C-NW-SW
Lease Owner Amerada Petroleum Corporation
Lease Name Henry May Well No. 1
Office Address Box 197, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-24- 19 61
Application for plugging filed 4-25- 19 61
Application for plugging approved 4-25- 19 61
Plugging commenced 10:30 AM 4-25- 19 61
Plugging completed 12:00 Noon 4-25- 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius
Producing formation - Depth to top - Bottom - Total Depth of Well 4470 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet for each plug set.
Filled hole with heavy mud to 400'
Spotted Cement plug from 400' to 338' W/20 Sax Cement.
Filled W/Heavy mud to 40'
Spotted Cement plug from 250' to 188' W/20 Sax Cement.
Filled W/Heavy Mud to 40'
Spotted Cement plug from 40' to top W/10 Sax Cement.
Started plugging @ 10:30 AM, finished @ 12:00 Noo. 4-25-61.

RECEIVED
STATE CORPORATION COMMISSION
05-01-1961
MAY 1 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Jelly Reaves Drilling Company
Address Box 1264, Cushing, Oklahoma

Kansas
STATE OF A.D. Simpson, COUNTY OF Barton, ss.
(employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A.D. Simpson
Box 197, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 61

My commission expires November 21, 1961
Charles W. Palmer Notary Public.



HENRY MAY NO. 1
C-NW-SW
Section 32-2S-30W

15-039-00125 - 00-00

DRILLER'S LOG:

<u>From</u>	<u>To</u>	
0'	200'	Sand
200'	1798'	Shale
1798'	1820'	Sand
1820'	2681'	Shale
2681'	2718'	Anhydrite
2718'	2730'	Shale
2730'	2870'	Shale & Lime
2870'	2980'	Shale
2980'	3036'	Sand
3036'	3067'	Shale
3067'	3170'	Lime
3170'	3360'	Shale
3360'	3392'	Sand
3392'	3417'	Lime
3417'	3605'	Shale
3605'	3671'	Lime
3671'	3741'	Shale
3741'	3748'	Sand
3748'	3770'	Shale
3770'	4190'	Lime
4190'	4260'	Shale
4260'	4270'	Lime
4270'	4345'	Shale
4345'	4470'	Lime
	4470'	T.D.

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1961

CONSERVATION DIVISION
Wichita, Kansas

Surface Casing Set @ 253' (8-5/8" OD 24# 8RT R2 E.W. Casing, ST&C, SH.)
Completed as Dry Hole.