

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-153-20760-00-00

API NUMBER ~~15-530-20760-~~

LEASE NAME Erickson

WELL NUMBER 11-24

1980' Ft. from S Section Line

2970' Ft. from E Section Line

SEC. 24 TWP. 2 RGE. 32 or (W)

COUNTY Rawlins

Date Well Completed 11-14-90

Plugging Commenced 7-2-92

Plugging Completed 7-2-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Schulein Company

ADDRESS 1776 Lincoln St #811 Denver, CO 80203

PHONE# (303) 839-5495 OPERATORS LICENSE NO. 6785

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 8, 1992 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Lancing Depth to Top 3776' Bottom 4024' T.D. 4070'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lancing</u>	<u>oil-water</u>	<u>Surface</u>	<u>269'</u>	<u>8 5/8"</u>	<u>269'</u>	<u>-0-</u>
		<u>Surface</u>	<u>4067'</u>	<u>5 1/2"</u>	<u>4067'</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 335 sack 65/35 poz mix down 5 1/2" casing - start w/ 15 sack & add 500# cotton seed hulls - pump remainder of cement. Pump against annulus & pressure to 600psi - annulus full. Shut 5 1/2" casing in @ 1500psi

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc. License No. _____

Address P.O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF KANSAS COUNTY OF KINGMAN, ss. JUL 17 1992

Carl W. Dorn Carl W. Dorn
Agent for CONSERVATION DIVISION (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Dorn

(Address) Rt 1 Box 16A S Milton KS 67106

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 92

TERRY L. ASMUSSEN
NOTARY PUBLIC
STATE OF KANSAS

Terry L. Asmusen
Notary Public

My Appt. Exp 9/22/93 My Commission Expires: SEPT. 22, 1993