

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rawlins County. Sec. 31 Twp. 2S Rge. (E) 32 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-SW-NE

Lease Owner Amerada Petroleum Corporation

Lease Name J. Hesterman Tract 1 Well No. 1

Office Address Box 197, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-15- 1959

Application for plugging filed 7-15-59 1959

Application for plugging approved 7-15- 1959

Plugging commenced 3:15 a.m. 7-15- 1959

Plugging completed 5:00 a.m. 7-15- 1959

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius, Hill City, Kansas

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4648' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	330'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton Spotted Cement Plugs As Follows:

567' to 600' W/20 Sacks

292' to 325' W/20 Sacks

0' to 31' W/10 Sacks.

Started Plugging at 3:15 a.m., finished at 5:00 a.m. 7-15-59 Under Supervision of Mr. A.D. Fabricius, State Plugging Supervisor.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Badger Drillers Inc,
Address 830 Mayo Bldg., Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
Ernest Higgins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Higgins

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1959

Charles H. Anderson

My commission expires November 21, 1961

Notary Public.

PLUGGING
FILE SEC. 31 T. 2 R. 32
BOOK PAGE 51 LINE 23

RECEIVED
STATE CORPORATION COMMISSION
7-21-59
JUL 21 1959

15-153-00054-00-00

AMERADA PETROLEUM CORP.
SW/4 NE/4 Sec. 31-2S-32W
Rawlins County, Kansas

Hesterman No. 1

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Remarks</u>
0	105	Surface shale	
105	240	Shale & sand	
240	330	Shale	Ran 8 jts. of 8-5/8" casing, set at 330' with 176 sacks cement.
330	1720	Shale	
1720	1940	Shale w/ sand	
1940	2140	Shale, shells & lime	
2140	2300	Shale & sand	
2300	2500	Shale & lime	
2500	2508	Shale	
2508	2530	Anhydrite (1st)	
2530	2715	Red Bed & shells	
2715	2744	Anhydrite (2nd)	
2744	3035	Red Bed & shale	
3035	3205	Shale & shells	
3205	3830	Shale & lime	
3830	3865	Lime	
3865	3900	Lime & shale	
3900	4170	Lime	
4170	4447	Lime & shale	
4447	4567	Lime & chert	
4567	4601	Lime (Mississippi)	
4601	4648	Lime (Arbuckle)	T. D. Dry hole.

I certify the above to be a true and exact copy of the Driller's Log as shown by the Daily Drilling Reports.

BADGER DRILLERS, INC.

J. O. Carver

Subscribed and sworn to before me this 22nd day of July, 1959.

Loris M. Jackson
Notary Public

My commission expires 9-28-61.

PLUGGING
FILE SEC. 31 T. 2 R. 32W
BOOK PAGE 51 LINE 23

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1959

CONSERVATION DIVISION
Wichita, Kas

7-27-59