

15-153-20002-00-00

Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Rawlins County, Sec. 16 Twp. 2S Rge. 32W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C NE NE

Lease Owner Okmar Oil Company

Lease Name Fleischacker Well No. 1

Office Address 1130 Wichita Plaza Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-20-67 19

Application for plugging filed 1-20-67 19

Application for plugging approved 1-20-67 19

Plugging commenced 1-20-67 19

Plugging completed 1-20-67 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4000 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8"	203'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug Set @ 600' with 20 sacks cement  
Plug set @ 210' with 20 sacks cement  
Plug set @ 40' with 10 sacks cement & 1/2 sk. hulls

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1967  
1-26-67  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
P. O. Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 67

(Signature) Glenda Nichols  
Notary Public.

My commission expires April 1, 1967

15-153-20002-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1967

1-26-67

CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S LOG

COMPANY:	Okmar Oil Company
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	FLEISCHACKER #1
LOCATION:	C NE NE SEC. 16-2S-32W
COMMENCED:	RAWLINS COUNTY, KANSAS
COMPLETED:	1-14-67
	1-20-67

-----		
0	203	Shale
203	1233	Shale, Shells
1233	1941	Shale, Sand Streaks
1941	1960	Anhydrite Streaks
1960	2255	Shale, Shells
2255	2331	Shale
2331	2359	Lime Streaks
2359	2555	Chalky Lime, Shale
2555	2595	Anhydrite
2595	2895	Shale, Redbed
2895	3750	Shale, Lime
3750	4000	Lime
	<u>4000</u>	<u>RTD - D. &amp; A.</u>

-----

8 5/8" 24# used surface casing set @ 203' cemented with 175 sacks of Common, 2% cc

-----

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Fleischacker #1 Well, located C NE NE of Section 16, Township 2 South, Range 32 West, Rawlins County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 24th day of January, 1967.

Ulanda Nichols  
Ulanda Nichols

My Commission Expires:  
April 1, 1967