

15-153-30115-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rawlins County, Sec. 4 Twp. 2S Rge. 32 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C/SE SE
Lease Owner Edwin Foster Blair & Associates - Murfin Drilling Co.
Lease Name GOELTL Well No. 1
Office Address 617 Union Center Bldg. - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1/13/61 19
Application for plugging filed 1/12/61 19
Application for plugging approved 1/13/61 19
Plugging commenced 1/13/61 19
Plugging completed 1/13/61 19
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug 400', displaced 20 sacks of cement through drill pipe.
Set 2nd plug 225', displaced 20 sacks of cement through drill pipe.
Set 3rd plug 40', displaced 10 sacks of cement through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

MAR 21 1961

CONSERVATION DIVISION
Wichita, Kansas

3-21-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center Building - Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin - Partner (employer, owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin
617 Union Center Bldg. - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of February, 19 61

My commission expires June 14, 1964
Mary Frances Blumel
Notary Public.



Hand Log Bureau

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15-153-30115-00-00


COMPANY Edwin Foster Blair & Associates - Murfin
Drilling Company
FARM GOELTL NO. 1

SEC. 4 T. 2S R. 32W
LOC. C/SE SE

TOTAL DEPTH 4460'
COMM. 1/2/61 COMP. 1/13/61

COUNTY Rawlins
KANSAS

SHOT OR TREATED
CONTRACTOR Murfin Drilling Company
ISSUED



CASING
20 10
15 8 5/8" 251'
12 6
13 5

ELEVATION 2918' KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 251' Sand & Shale
- 1425' Shale
- 1914' Shale, Sand Pyrite
- 2260' Shale & Pyrite
- 2337' Shale, Sand & Pyrite
- 2367' 1st Anahydrite
- 2440' Shale and Sand
- 2610' Shale and Shells
- 2697' Anahydrite
- 3200' Shale & Shells
- 3565' Shale & Lime
- 3855' Lime & Shale
- 4075' Lime
- 4195' Lime & Shale
- 4258' Lime
- 4360' Lime, Shale & Sand
- 4430' Lime & Shale
- 4460' Lime

ELECTRIC LOG TOPS:

- Anahydrite 2660'
- Base/Anahydrite 2698'
- Top Admire 3489'
- Top Topeka 3682'
- Top Oread 3781'
- Top Heebner 3792'
- Top Lansing 3834'
- Base/Kansas City 4085'
- Top Marmaton 4131'
- Top Cherokee 4238'
- Conglomerate 4286'
- Top Arbuckle 4395'
- Total Depth 4460'

DST #1 3734'-3795' Open 1 hr.
Recovered 100' of mud with a few
specks of oil. IF 0# FF 0#
BHP 1060#/20 min.

DST #2 3840'-3900' Open 1 hr.
Recovered 10' clean oil, 10' heavy
oil cut mud, and 60' muddy water.
IF 0# FF 0# BHP 300#/20 min.

DST #3 3932'-3988' Open 1 hr.
Recovered 60' salt water, 120'
of salty mud. IF 0# FF 0#
BHP 1080#/20 min.

DST #4 4014'-4058' Open 1 hr.
Recovered 30' mud, 60' muddy water.
IF 0# FF 0# BHP 490#/20 min.

RECEIVED
STATE OCCUPATION COMMISSION

MAR 21 1961

CONSERVATION DIVISION
Wichita, Kansas

3-21-61

State of Kansas
County of Sedgwick

I, W. R. Murfin of the Murfin Drilling Company
upon oath state that the above and foregoing is a true and correct
copy of the log of the GOELTL #1 well.

W. R. Murfin

Subscribed and sworn to before me this 20th day of March 1961

My Commission Expires: June 14, 1964

May James Blinn
Notary Public