



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1969
CONSERVATION DIVISION
Wichita, Kansas
10-6-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Graves Drilling Company,

Complete Address: 505 Union Center Building, Wichita, Kansas.

Lease Name: Zadina Well No. 1

Location: CNW-NW Sec. 2 Twp. 2 Rge. (E)(W) 35

County: Rawlins Total Depth 3165' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

269'--8 5/8" Surface casing, cement circulated.

Circulate hole with heavy mud. Pull DP to 1860' and displace 100 Sx. cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent