

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22159-00-00  
Spot: NE Sec/Twnshp/Rge: 20-25S-13W  
3960 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: SHRACK Well #: 1  
County: STAFFORD Total Vertical Depth: 4500 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

CIBP Size: feet: 3530 WITH 2 SX CMT  
PROD Size: 7 feet: 4430 WITH 100 SX CMT  
SURF Size: 10.75 feet: 300 WITH 250 SX CMT

\$ 146<sup>25</sup>

Well Type: SWD UIC Docket No: D23764.0 Date/Time to Plug: 07/13/2004 10:15 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: KENNETH C GATES Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: CIBP @ 3530' & 2 SX CMT. PLUG AT 800' WITH 80 SX CMT. PLUG AT 320' WITH 60 SX CMT. PLUG AT 40' WITH 30 SX CMT. 15 SX GEL FOR SPACER.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/13/2004 11:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG SET CIBP @ 3530' & 2 SX CMT. 2ND PLUG RUN 2 3/8" TUBING TO 792'.  
LOAD HOLE WITH MUD & PUMP 80 SX CMT. 3RD PLUG PULL TUBING TO 312' &  
PUMP 60 SX CMT. 4TH PLUG PULL TUBING TO 30' & FILL SURFACE CASING WITH  
15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4430	4500		
4304	4314		

RECEIVED  
JUL 21 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1578' OF 7" CASING.

Plugged through: TBG

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE 7-21-04  
INV. NO. 2005.06.0136