

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20027-00-01
Spot: NWNENW Sec/Twnshp/Rge: 13-16S-27W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HORCHEM Well #: 1
County: LANE Total Vertical Depth: 4681 feet

Operator License No.: 9615
Op Name: GERSTNER, JOE
Address: 302 E. SYCAMORE
NESS CITY, KS 67560

MSCC Size: feet: 2050 CMT TO SURFACE
PROD Size: 5.5 feet: 4598
SURF Size: 8.625 feet: 330 WITH 200 SX CMT

#152¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2004 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: WAYNE Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PER KCC. 30 SX CMT. ON BOTTOM WITH 200#S HULLS THEN GEL SPACER TO 2100'. CEMENT TO SURFACE. HAS BEEN DV'D FROM 2050'.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2004 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4558'. PUMPED 40 SX CMT & 400# HULLS. PUMPED 16 SX GEL & 170 SX CMT. MAXIMUM PRESSURE 100#. WENT ON VACUUM. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# AND HELD. CMT FELL 250'. TOPPED OFF WITH 30 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
4440	4446		
4224	4228		
4196	4202		
4132	4135		
4104	4108		

RECEIVED
JUL 21 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Michael Maier

(TECHNICIAN)

INVOICED

DATE 7-21-04

INV. NO. 2005060129

Form *[Signature]*