

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20756-00-01  
Spot: SWSENE Sec/Twnshp/Rge: 20-25S-13W  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SHRACK Well #: 2 OWWO  
County: STAFFORD Total Vertical Depth: 4378 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

CIBP Size: feet: 4300 WITH 2 SX CMT  
PROD Size: 5.5 feet: 4377 WITH 100 SX CMT  
SURF Size: 8.625 feet: 462 WITH 350 SX CMT

*\$142<sup>29</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2004 2:00 PM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: BRAD TATSO Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: CIBP @ 4300' & 2 SX CMT. PLUG AT 800' WITH 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/09/2004 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4300' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 5 1/2" CASING & RUN 2 3/8" TUBING IN TO PLUG THROUGH. 1ST PLUG AT 800' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4344	4346		
4336	4338		
4320	4323		

RECEIVED  
JUL 21 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1621' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED

DATE 7-21-04

INV. NO. 2005060136

Form SP-13