

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02665-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 3-13S-17W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCHMIDT B Well #: 1
County: ELLIS Total Vertical Depth: 3557 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

PROD Size: 5.5 feet: 3544
SURF Size: 8.625 feet: 170

115⁶⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2004 9:00 AM
Plug Co. License No.: 31287 Plug Co. Name: RANDY'S WELL SERVICE, INC.
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 628-3749

Proposed Plugging Method: Ordered 325 sxs cement and 500# hulls.

Plugging Proposal Received By: ROGER MOSES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2004 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Fish (rods/tubing) at 1300'.
Perforated at 675'.
Ran tubing to top of fish at 1270' and circulated with 85 sxs cement.
Pulled all tubing and squeezed 5 1/2" casing with 165 sxs cement and 300# hulls.
Max. P.S.I. 1100#. S.I.P. 500#.
Tied to 8 5/8" x 5 1/2" annulus and squeezed 5 sxs cement to 300# P.S.I.
Well locked up.
Total of 250 sxs 60/40 pozmix - 10% gel and 300# hulls.

RECEIVED
JUL 21 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. BLACKHAWK TANK-WATER.

Plugged through: TBG

District: 04

RD.

Signed

Roger D. Moses

(TECHNICIAN)

INVOICED

DATE 7-21-04

INV. NO. 2005060126

Form CP-2/3

JUL 16 2004

EARL F WAKEFIELD #1 SCHMIDT 'B' 3-13-17W 3A
 SW SW NE

Contr. EARL F WAKEFIELD ELLIS County

E 2031 Comm. _____ Comp. 7-19-57 IP 164 BOPD/ARB
 PHY POT

Tops	Depth	Datum
Arh	1211	+ 820
KC	3280	-1249
B/KC	3518	-1487
CONG	3524	-1493
ARB	3540	-1509
ID	3557	-1526

Casing
 8" 170
 5" 3544
 DST 3326-50/1 HR, 720' G, 130'
 H OCM, BHP 830#
 DST 3380-94/30", 8' MUD, NO BHP
 DST 3544-56/1 HR, 60' FR O,
 110' H OCM, BHP 960#
 DP: SWB 40 BO
 CATHARINE POOL PH, NW/24 HRS.

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS