

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21089-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 18-9S-23W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KLENK Well #: 4
County: GRAHAM Total Vertical Depth: 4000 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3998 150 SX CMT
SURF Size: 8.625 feet: 207 175 SX CMT

\$130⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2004 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed
Plugging
Method:

Plugging Proposal Received By: DENNIS HAMEL WitnessType: NONE
Date/Time Plugging Completed: 06/15/2004 10:30 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Pumped down 5 1/2" casing with 25 sxs cement and 500# hulls, followed with 20 sxs gel and 180 sxs cement.
Max. P.S.I. 1000#. Shut in.
Pumped down annulus - no cement - pressured to 400#.

Perfs:

Top	Bot	Thru	Comments
3922	3929		
3882	3888		

RECEIVED
JUL 21 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 7.21.04
INV. NO. 2005060128

JUL 15 2004

JOHN O. FARMER, INC.
P.O. BOX 352

#4 KLENK

18-9-23W
SE NW NE

RUSSELL, KS 67555
CONTR JOHN O. FARMER

CTY GRAHAM

GEOL SAM L. FARMER

FIELD ERNST NW

E 2391 KB CM 1/8/79 CARD ISSUED 3/24/79 IP P 65 BO + TR WTR
LKC 3882-88 & 3922-29

+	+	+
+	+	+
+	+	+

API 15-065-21,089

LOG	TOPS	DEPTH	DATUM
ANH	2054	+ 337	
HEEB	3686	-1295	
TOR	3714	-1323	
LANS	3732	-1341	
BKC	3958	-1567	
LTD	3998	-1607	
RTD	4000	-1609	

8-5/8" 207/175sx, 5 1/2" 3998/150sx
DV TOOL 2060
DST (1) 3770-90/30-60-60-60, 480 GIP,
60 OCM, 180 MCO, SIP 480-387#, FP
20-40#/61-81#
DST (2) 3910-55/30-60-60-60, 120 GIP,
120 MDY GSY O, (60% O), SIP 602-
265#, FP 20-30#/50-51#
MICT - CO, PF (LKC) 28/3922-29, AC 2000,
WOULD NOT TAKE, RE-PF 3922-29, SWB PT LD
& SWB 3 BFPH, 75% O, AC 2000, SWB 28
BFPH, 75%, SWB PT LD & SWB 8 BFPH, 97%
O

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS