

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21053-00-01
Spot: SESWNE Sec/Twnshp/Rge: 18-9S-23W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KLENK OWWO Well #: 3
County: GRAHAM Total Vertical Depth: 3969 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

PROD Size: 4.5 feet: 3962 150 SX CMT
SURF Size: 8.625 feet: 212 170 SX CMT

\$128⁹⁹

Well Type: EOR UIC Docket No: E24818.4 Date/Time to Plug: 06/15/2004 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed
Plugging
Method:

Plugging Proposal Received By: DENNIS HAMEL WitnessType: NONE
Date/Time Plugging Completed: 06/15/2004 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Pumped down 4 1/2" casing with 25 sxs cement and 500# hulls, followed with 15 sxs gel and 200 sxs cement.
Max. P.S.I. 900#. Shut in.
Pumped down annulus - no cement - pressured to 500#.

Perfs:

Top	Bot	Thru	Comments
3871	3875		

RECEIVED
JUL 21 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE

7-21-04

INV. NO.

2005060128

JUL 15 2004

JOHN O FARMER
RUSSELL KS 67665

18-09S-23W
SE SW NE

3 KLENK OWWO

site: 5 S & 2-1/4 E OF PENOKEE KS	ty: GRAHAM	API 15-065-21053
contr: UNKNOWN	field: ERNST NW	
geol: NONE		
fr date 01/15/96	spd date 12/26/95	drig comp 12/26/95
	card issued 01/15/96	last revised 01/15/96

ELV: 2381 KB, 2376 GL LOG
tops.....depth/datum
ANH.....2038 + 343
HEEB.....3676 -1295
TOR.....3702 -1321
LANS.....3718 -1337
PBTD.....3901 -1520
BKC.....3940 -1559
LTD OLD.....3969 -1588
RTD OLD.....3969 -1588

IP status:
 INJ, LKC 3871-3875 , 12/27/95
 OLD INFO: OPERATOR WAS JOHN O FARMER, 3
 KLENK, SPD 09/30/78 , 10/08/78 8-5/8" 212 / 170 SX, 4-
 1/2" 3962 / 150 SX, DV TOOL AT 2060 / 325 SX, OIL, P 100
 BOPD, NW, LKC 3871-3875 , 10/26/78 (CARD ISSUED
 11/02/78)
 CONTR: JOHN O FARMER
 NO CORES
 DST (1) 3860-3880 (LKC), / 45-45-60-60, 210' GIP, REC 90'
 HO & GCM ISIP 382# FSIP 283# IFP 21# -32# FFP 43#
 -65#

COPYRIGHT 1996
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

JOHN O FARMER
RUSSELL KS 67665

18-09S-23W
SE SW NE

3 KLENK OWWO

DST (2) 3896-3921 (LKC), / 45-45-45-45, REC 20' V SLI OCM ISIP 53# FSIP 53# IFP 21# -21#
 FFP 21# -42#
 MICT - CO, PF (LKC) 16/3871-3875, AC 2000 GAL (15% NE), SWB 7 BOPH, NW/5 HRS, SET 2-3/8"
 TBG & PKR AT 3544, P 100 BOPD, NW, 10/26/78
 NEW INFO: FR 01/15/96 , REWORKED 12/26/95 DC 12/26/95 MICT - CO, PB 3901 TD, TSTD OLD
 PFS (LKC 3871-3875), CONVERTED TO WIW - INJECTION RATE SATISFACTORY, 12/27/95

MAADICED