

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-153-20002-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1967
1-22-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name Fleischacker Well No. 1

Location CNE-NE Sec. 16 Twp. 2 Rge. (E) (W) 32

County Rawlins Total Depth 4000

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No. _____

Operation Completed: Hour 4:00PM Day 20 Month 1 Year 1967

The Above well was plugged as follows:

203'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sk. hulls

and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/23/67
INV. NO. 4644-W

Signed: A. L. Nichols
Well Plugging Supervisor