

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1970

CONSERVATION DIVISION  
Wichita, Kansas

10-26-70

15-153-20095-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name Tettera Tettera Well No. 1

Location CSE-SW Sec. 11 Twp. 2 Rge. (E) (W) 32

County Rawlins Total Depth 3883'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.     

Operation Completed: Hour 5:30 AM Day 21 Month 10 Year 1970

The above well was plugged as follows:

266'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1475'.

Circulated hole with heavy mud. Pulled DP to 1750' and displaced 100 Sx. cement thru  
DP from 1750' to 1425'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. S. Daniels  
Well Plugging Supervisor

DATE 10/26/70  
INV. NO. 2754-W