

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20109-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 5 1971
CONSERVATION DIVISION
Wichita, Kansas
4-5-71

Operator's Full Name Murfin Drilling Company,
Complete Address 617 Union Center, Wichita, Kansas.
Lease Name Pitner Well No. 1
Location CNW-SE Sec. 11 Twp. 2 Rge. (E) (W) 32
County Rawlins Total Depth 3945'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 10:00 PM Day 2 Month 4 Year 1971

The above well was plugged as follows:

117'--8 5/8" Surface casing, cement circulated with 110 Sx.
Top of Dakota section @ 1625'.

Circulated hole with heavy mud. Pulled DP to 1850' and displaced 100 Sx. cement thru
DP from 1850' to 1525'. Pulled DP to 125' and displaced 20 Sx. cement thru DP from
125' to 65'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 4/6/71
INV. NO. 3506-W