

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20129-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas
12-10-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Inc., & National Oil Company.

Complete Address Suite 905, Century Plaza, Wichita, Kansas.

Lease Name Goelbl Well No. 1

Location SE-SW-NW Sec. 4 Twp. 2 Rge. (E) (W) 32

County Rawlins Total Depth 4075'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address 905 Century Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 1:30 PM Day 5 Month 12 Year 1971

The above well was plugged as follows:

272'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1750'.

Circulated hole with heavy mud. Pulled DP to 1975' and displaced 110 cu. Ft. cement
Thru DP from 1975' to 1650'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. G. Zichels
Well Plugging Supervisor

INVOICED

DATE 12/10/71

INV. NO. 4798-W