

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21214-00-00
Spot: SENE Sec/Twnshp/Rge: 28-32S-32W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: ALEXANDER TRUST Well #: A 1
County: SEWARD Total Vertical Depth: 6050 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

MSCC Size: feet: 3247 WITH 175 SX CMT
PROD Size: 5.5 feet: 6049 WITH 225 SX CMT
SURF Size: 8.625 feet: 1596 WITH 685 SX CMT

\$196⁶³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/30/2004 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 5510' & 5 SX CMT. PLUG AT 1620' WITH 50 SX CMT. PLUG AT 800' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2004 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6016'. SAND BOTOM OFF TO 5487' WITH 5 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE WITH CASING TO 1620'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 800'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE

Perfs:


Top	Bot	Thru	Comments
5922	5932		
5560	5570		

RECEIVED
JUL 15 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 2220' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE

7-16-04

TV. NO.

2005060066

Form CP-1/3