

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21568-00-00
Spot: W2SESENE Sec/Twnshp/Rge: 28-33S-40W
2310 feet from N Section Line, 500 feet from E Section Line
Lease Name: LYNCH Well #: B 2
County: MORTON Total Vertical Depth: 6250 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

MSCC Size: feet: 3000 WITH 75 SX CMT
PROD Size: 5.5 feet: 5850 WITH 160 SX CMT
SURF Size: 8.625 feet: 1636

13
\$203

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/01/2004 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 20 SX CMT. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 550' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: PARTIAL
Date/Time Plugging Completed: 07/01/2004 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PBTD 5690'. PUMP 400# HULLS WITH 20 SX CMT. DISPLACE TO BOTTOM WITH 130 BBL MUD. PRESSURE UP & SHUT IN. SHOT OFF CASING AT 2427'. WOULD NOT COME LOOSE. SHOT OFF AT 1810', CAME LOOSE. 1ST PLUG PULL OUT OF HOLE TO 1650'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH 33 BBL MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. LOAD HOLE & PUMP 30 SX CMT. DISPLACE WITH 10 BBL MUD. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5624	5706		

RECEIVED
JUL 15 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1810' OF 5 1/2" CASING.
Plugged through: CSG

District: 01

RECEIVED
JUL - 6 2004
KCC Dodge City

Signed Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 7-16-04
INV. NO. 2005060061

Form 2/3