

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: 15-159-21608-00-00
Spot: ~~SEN~~WNENE Sec/Twnshp/Rge: 6-21S-6W
4833 feet from S Section Line, 1002 feet from E Section Line
Lease Name: WOLF B Well #: 7-6
County: RICE Total Vertical Depth: 3519 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3547
SURF Size: 8.625 feet: 213

#114 37

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2004 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,425' & top with 5 sxs. cement. Shoot casing off. Pull casing to 1,050' & spot 35 sxs. cement. Pull casing to 625' & spot 35 sxs. cement. Pull casing to 265' & circulate cement at the surface.

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 06/15/2004 7:00 PM

Witness Type: PARTIAL
KCC Agent: MICHAEL WILSON

RECEIVED
KCC DISTRICT #2
JUN 17 2004
WICHITA, KS

Actual Plugging Report:

Perfs:

Sanded to 3,420' & topped with 5 sxs. cement. Shot casing off at 1,800'. Pulled casing to 1,028' & spotted 35 sxs. cement w/100# hulls. Pulled casing to 589' & spotted 35 sxs. cement w/200 # hulls. Pulled casing to 333' & circulated 125 sxs. cement to the surface.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 21 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #24498.

Plugged through: CSG

District: 02

Signed Michael R Wilson
(TECHNICIAN)

INVOICED
DATE 7-14-04
INV. NO. 2005060058