

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22469-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 26-34S-39W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SULLIVAN Well #: B-2  
County: STEVENS Total Vertical Depth: 6840 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

CIBP Size: feet: 6025  
PROD Size: 5.5 feet: 6538 WITH 220 SX CMT  
SURF Size: 8.625 feet: 1740 WITH 470 SX CMT

# 22230

Well Type: DH UIC Docket No: Date/Time to Plug: 06/29/2004 3:00 PM  
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE  
Proposal Rcvd. from: RICKY ESCABEDO Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: BULLHEAD 2 SX HULLS & 20 SX CLASS H CMT TO PLUG PERFS. CUT OFF 5.5" CSG@ FREE POINT. SET CMT PLUGS AS FOLLOWS; 50 SX FROM 1650'-1800', 40 SX FROM 429'-550'; 10 SX FROM 4'-40'; CUT OFF & CAP 8.625" 4' BELOW G.L.

Plugging Proposal Received By: JIM HOLLAND  
Date/Time Plugging Completed: 06/29/2004 9:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 300# HULLS WITH 30 SX CMT. DISPLACE TO BOTTOM WITH MUD. PRESSURE TO 500 PSIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1780'. CIRCULATE HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. CIRCULATE HOLE & PUMP 40 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5984	5990		

RECEIVED  
JUL 15 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland  
(TECHNICIAN)

INVOICED  
DATE 7-16-04  
INV. NO. 2005060661

FORM CR-13