

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19497-00-00

Spot: NESWNW

Sec/Twnshp/Rge: 8-26S-5E

3643 feet from S Section Line, 4250 feet from E Section Line

Lease Name: ELDORADO TANK FARM

Well #: 1

County: BUTLER

Total Vertical Depth: 2800 feet

Operator License No.: 33394

PROD Size: 4.5 feet: 2358

Op Name: SHELL PIPELINE CO. LP

SURF Size: 7 feet: 2415

Address: 3913 SW 10TH ST.

EL DORADO, KS 67042

\$91.00

Well Type: SWD

UIC Docket No: D07177.0

Date/Time to Plug: 04/20/2004 12:00 PM

Plug Co. License No.: 5870

Plug Co. Name: PHILLIPS WELL SERVICE, INC.

Proposal Rcvd. from: DAN RAFFERTY

Company: SHELL PIPELINE CO. LP

Phone: (316) 321-4645

Proposed
Plugging
Method:

See actual report.

RECEIVED
KCC DISTRICT #2

MAY 13 2004

WICHITA, KS

Plugging Proposal Received By: DONALD HOBERECHT

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/20/2004 3:00 PM

KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Perfs:

MIRU - unseat packer. Pulled packer and tubing. Ran CIBP to 2295' and set. Put 3 sacks of cement on CIBP with bailer. Set CIBP at 290'. Bailed casing dry. Filled casing with 1 yard slurry mix to surface.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 25 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: LEWIS & WEST REDI MIX #81693

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

INVOICED

DATE

5-25-04

INV. NO.

2004061602

Form CP-2/3