

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20843-00-01
Spot: SWNENW Sec/Twnshp/Rge: 11-32S-42W
4060 feet from S Section Line, 3860 feet from E Section Line
Lease Name: JACKSON O W W O Well #: 2-11
County: MORTON Total Vertical Depth: 5400 feet

Operator License No.: 32782
Op Name: DUKE ENERGY FIELD SERVICES, LP
Address: 370 17TH ST., STE. 2500
DENVER, CO 80202

CIBP Size: feet: 4895 WITH 20 SX CMT
PROD Size: 4.5 feet: 5395 WITH 535 SX CMT
SURF Size: 9.625 feet: 1665 WITH 500 SX CMT

\$175⁵⁰

Well Type: GW UIC Docket No: _____ Date/Time to Plug: 06/01/2001 12:00 PM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RUSSELL BENTLEY Company: DUKE ENERGY FIELD SERVICES Phone: (303) 595-3331

Proposed Plugging Method: CIBP @ 4895' WITH 20 SX CMT. PLUG AT 1900' WITH 50 SX CMT. PLUG AT 1700' WITH 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2004 7:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 5364'. SET CIBP @ 4895' WITH 20 SX CMT ON TOP. 1ST PLUG CIRCULATED HOLE WITH MUD AT 1900' & PUMP 50 SX CMT. 2ND PLUG PULLED TO 1700' & PUMPED 75 SX CMT. 3RD PLUG PULLED UP TO 600' & SPOT 50 SX CMT. 4TH PLUG PULLED TO 40' & PUMPED 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5083	5088		
5060	5072		
4994	5006		

RECEIVED
JUN 04 2004
KCC WICHITA

Remarks: USED CLASS H CMT BY EAGLE WELL SERVICE. RECOVERED 1900' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
JUN - 2 2004
KCC Dodge City

Signed

Kevin D Strube

(TECHNICIAN)

INVOICED

DATE

6-4-04

INV. NO.

2004061639

Form *[Signature]*