

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-07197-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 35-19S-12W  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: HAMMER A Well #: 2  
County: BARTON Total Vertical Depth: 3384 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S. YALE #609  
TULSA, OK 74136

PROD Size: 5.5 feet: 3343 135 SX CMT  
SURF Size: 8.625 feet: 274 150 SX CMT

#109<sup>98</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/15/2004 10:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed  
Plugging  
Method:

Ordered 540 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/15/2004 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech perfed at 1450' and 617'.  
Classic Well Service RIH with tubing to 2700'.  
Allied tied onto tubing and pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.  
Pulled tubing to 1500' and pumped 190 sxs 60/40 pozmix with 100# hulls mixed in.  
Left set two hours.  
Pulled to 800' and pumped 70 sxs 60/40 pozmix to circulate cement to surface.  
Pulled tubing and topped with 130 sxs 60/40 pozmix with 100# hulls mixed in.  
5 1/2" casing was standing full.  
Tied onto backside with a swedge and pumped 50 sxs cement.  
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3339	3347		
3095	3330		


RECEIVED  
JUL 20 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #17840.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE

7-20-04

INV. NO.

2005060091

Form CP-2/3

JUL 16 2004

DATE

INDICED

W L HARTMAN #2 HAMMER 'A' 35-19-12W NW SE NW

Contr. BARTON County

E 1805 Comm. 6-17-45 Comp. 7-26-45 IP 75 BOPD

Tops	Depth	Datum	Casing
ANH	600		5" 3343
BR IM	3075		FU 500' oil/10 hr: A/500 1/4 BOPH: DD. 3348: Pmp 5 BOPH/6 hr
LANS	3095		
ARB	3343		
TD	3346		


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS