

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03129-00-01
Spot: NWSWSW Sec/Twnshp/Rge: 12-9S-17W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MCCLAY Well #: 4
County: ROOKS Total Vertical Depth: 3446 feet

Operator License No.: 5147
Op Name: BEREDCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

CIBP Size: feet: 3916
PROD Size: 5.5 feet: 3440 150 SX CMT
SURF Size: 8.625 feet: 206 150 SX CMT

#112⁰⁰

Well Type: EOR UIC Docket No: E10108.1 Date/Time to Plug: 07/13/2004 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DENNIS KIRMER Company: BEREDCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 500# hulls.
DV at 883' to surface with 200 sxs.
Fish in the hole - tubing & packer - fish at 1090'.
Fluid level 160'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2004 12:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well service RIH with tubing to 1042'.
Allied tied onto tubing and pumped 120 sxs neat - Cement circulated to surface.
Pulled tubing and tied onto 5 1/2" casing with a swedge.
Pumped 100 sxs 60/40 pozmix with 500# hulls mixed in.
Max. P.S.I. 1000#. S.I.P. 450#.
Tied onto backside - pumped 80 sxs 60/40 pozmix.
Max. P.S.I. 200#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3361	3371		
3342	3350		
3324	3326		
3319	3324		
3315	3319		
3255	3265		
3213	3223		


RECEIVED
JUL 15 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #17045.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)



INVOICED

DATE

7-16-04

INV. NO.

2005060063

Form CP-2/3

JUL 13 2004

DRAIN

INVOICE

COOP REF. ASS'N #4 McClAY 23 12-9-17W
 A/B NW SW SW

Contr. _____ ROOKS _____ County

E. 2038 Comm. 5-1-49 Comp. 7-8-49 IP 25 BOPD

Tops	Depth	Datum
Arb 7/8	1233	
B	1270	
HEEB	3119	-1081
TOR	3140	-1102
LANS	3161	-1123
ARB	3140	-1402
T.D.	3146	-1408

Casing

8" 206 ACID 500
 5" 3140 PMP 150 80/8 HRS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS