

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20259-00-00
Spot: SENWSW Sec/Twnshp/Rge: 12-10S-24W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BEESLEY Well #: 5
County: GRAHAM Total Vertical Depth: 4251 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 4.5 feet: 4251 w/225 sxs cmt
SURF Size: 8.625 feet: 196 w/150 sxs cmt

9138¹⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2004 7:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 200 sxs Swift Multi-Density - 500# hulls.
D.V. Tool. PBTD 4207'. Top of fish 2105'. Fluid level 2100'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2004 9:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Swift Services pumped 25 sxs neat, followed with 150 sxs cement with 500# hulls.
Max. P.S.I. 500# S.I.P. 400#.
Hooked up backside instant 500#.

RECEIVED
JUL 15 2004
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS GANO UNIT #2-5. SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

7-16-04

WT. NO.

2005060065

Form CP-2/3

JUL 14 2004

48 1/2" STAB
 INDICES

Currently Gano Unit 2-5

DON E. PRATT #5 BEESLEY 12-10-24W
 HAYS, KS. SE NW SW
 Contr. GARVEY DRLG. Cty. GRAHAM
 Geol. J. R. GREEN Pool GANO SE

E. 2497 KB Cm. 9/20/69 Cp. 10/30/69 IP PMP 270 BOPD, NW/
 LANS 3996-4000

API 15-065-20,259

SMP Tops	Depth	Datum	Csg.
ANH	2111	+ 386	8-5/8" 199/150 SX
B ANH	2152	+ 345	4 1/2" 4251/225 SX
TOP	3565	-1068	
HEEB	3777	-1280	PF 6/3996-4000, SWB DN & SWB
TOR	3801	-1304	31 1/2 BOPH, NW/3 HRS, 500' OB,
LKC	3818	-1321	ACID 250, POP
BKC	4046	-1549	
CHER SD	4254	-1757	
RTD	4265	-1768	

NO DSTS
NO LOG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS