

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22665-00-00
Spot: SESWNW Sec/Twnshp/Rge: 23-6S-24W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: WHITE Well #: 1
County: GRAHAM Total Vertical Depth: 4210 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W. MAIN - PO BOX 428
LOGAN, KS 67646

PROD Size: 5.5 feet: 4218 500 SX CMT
SURF Size: 8.625 feet: 254 165 SX CMT

83
#136

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2004 11:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JIM R BAIRD Company: BAIRD OIL COMPANY, LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered out 200 sxs Swift Multi-Density cement - 18 sxs gel spacer - 500# hulls.
D.V. tool at 2114' with no cement amounts.
PBTD 4156'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2004 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 50 sxs SMD with 500# hulls, followed with 18 sxs gel spacer.
Topped off with 100 sxs SMD.
Max. P.S.I. 1000#. S.I.P. 500#.
Backside 500# instant pressure.

Perfs:

Top	Bot	Thru	Comments
3715	3858		

RECEIVED
JUL 15 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed _____

Richard Williams

(TECHNICIAN)

INVOICED

DATE

7-16-04

INV. NO.

2005060062

Form CP-2/3

JUL 14 2004

STATE: KANSAS COUNTY: GRAHAM REISSUE 23-6S-24W
FIELD: HOOSIER 3 1/2 MI SE INDIANA FLD SE SW NW
OPER: HESS OIL 2970 FSL 4180 FEL SEC
WELL: 1 WHITE WELL CLASS: WFD ELEV: 2450 KB
API: 15-085-22665 STATUS: OIL 2442 GR
SPUD: 03/23/92 COMP: 04/10/92
DTD: 4210 LTD: FTD: ARBUCKLE PBTD:

LOC: 10 MI SE LENORA, KS

IP: COMP 4/10/92, IPP 95 BO, 15 BWPD, GTY 27 PROD ZONE- LANSING-K C
3715-3858(GROSS)
NO CORES, FOUR DSTS (LANSING-KANSAS CITY DISCOVERY-NEW FIELD)

LOG TOPS:

STONE CORRAL	2152 298	LANSING	3714 -1264
B/ STONE CORRAL	2186 284	B/ KANSAS CITY	3897 -1447
TOPEKA	3470 -1020	PENNSYLVANIAN	4007 -1557
HEEBNER	3671 -1221	ARBUCKLE	4200 -1750

TD 4210 -1760

LOG TYPES: GRDL, SONL;

CSGS: 8 5/8 @ 255 W/165 SX, 5 1/2 @ 4208 W/500 SX; TBG: 2 7/8 @ 3933; DRLG COMP
03/31/92 RIG REL 03/31/92

(OVER)

COPYRIGHT 1994 PETROLEUM INFORMATION CORPORATION

DATE 08/05/94 CARD # 00041-KS

STATE: KANSAS COUNTY: GRAHAM REISSUE 23-6S-24W
FIELD: HOOSIER 3 1/2 MI SE INDIANA FLD SE SW NW
OPER: HESS OIL 2970 FSL 4180 FEL SEC
WELL: 1 WHITE WELL CLASS: WFD
(CONTINUED)

DSTS: DST # 1 (TOPEKA) 3630-3688, OP 30 MIN, SI 45 MIN, OP 1 HR, SI 45 MIN, REC:
1965 FT WTR, IFP 201, FFP 538, IFP 634, FFP 932, ISIP 1267, FSIP 1248, IHP 1843,
FHP 1824, BHT 108 DST # 2 (LANSING) 3704-3750, OP 1 HR, SI 45 MIN, OP 1 HR,
SI 45 MIN, REC: 120 FT GAS, 1240 FT OIL, IFP 144, FFP 355, IFP 413, FFP 519, ISIP
1267, FSIP 1257, IHP 1988, FHP 1920, BHT 109 GTY 24 DST # 3 (LANSING)
3750-3810, OP 1 HR, SI 45 MIN, OP 1 HR, SI 45 MIN, REC: 220 FT SOCM, 480 FT
MCSWTR, IFP 125, FFP 259, IFP 298, FFP 384, ISIP 1163, FSIP 1124, IHP 2026, FHP
1998, BHT 109 DST # 4 (LANSING) 3810-3900, OP 1 HR, SI 45 MIN, OP 1 HR, SI 45
MIN, GAS TS 2ND OPEN REC: 2108 FT OIL, IFP 163, FFP 515, IFP 605, FFP 798, ISIP
1343, FSIP 1333, FHP 1920, BHT 110;

PRODUCING INTERVAL: PERF (LANSING-KANSAS CITY) 3715-3858 GROSS,

OPER ADD: BOX 1009, MCPHERSON, KS, 67460 PHONE (316) 241-4640;

CONTR: MALLARD DRLG

GEOL: JAMES C HESS

WELL ID CHANGES: ELEV CHGD FROM 2450 TS;
REISSUED TO ADD NEWLY RELEASED

(CONTINUED ON NEXT CARD)

COPYRIGHT 1994 PETROLEUM INFORMATION CORPORATION

DATE 08/05/94 CARD # 00041-KS