

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-30289-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 13-17S-11W  
1650 feet from N Section Line, 990 feet from E Section Line  
Lease Name: KRAFT-PRUSA UT Well #: 8-8  
County: BARTON Total Vertical Depth: 3320 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

CIBP Size: feet: 1255  
PROD Size: 4.5 feet: 3319 100 SX CMT  
SURF Size: 8.625 feet: 631 500 SX CMT

#107<sup>90</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/12/2004 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JODY SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/12/2004 12:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1255' and 640'.  
Tied onto 4 1/2" and pumped 150 sxs 60/40 pozmix - 10% gel cement with 400# hulls.  
Cement circulated up backside.  
Backside shut in.  
Pumped 10 sxs cement.  
Max. P.S.I. 400#. S.I.P. 350#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3102 | 3224 |      |          |

RECEIVED  
JUL 15 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Case Morris  
(TECHNICIAN)

**INVOICED**

DATE 7-16-04  
INV. NO. 2005060060

JUL 14 2004

5-17

MAP NO. \_\_\_\_\_

SEC. \_\_\_\_\_ 13-17S-11W

STATE Kansas COUNTY Barton

LOC. \_\_\_\_\_ NW SE NE

OPER. Sunray DX Oil Company - Great Bend, Kansas FT/FR \_\_\_\_\_ LINE

WELL #WI-8 FARM Kraft Prusa Unit - Tract 8 FT/FR \_\_\_\_\_ LINE

POOL Kraft Prusa (Multi-Pay) ELEV. 1858 GR. 1866 DF. 1869 KB

CONT. Stickle Drilling GEOL. \_\_\_\_\_

CO. \_\_\_\_\_

INT. \_\_\_\_\_


F.R. 4-21-65 SPUD 4-22-65 COMP. 5-6-65

TD. 3320 FM. Arb PBTD. \_\_\_\_\_

WIW in Kc 3102-3224

8" @631' w/500 Sx.

4 1/2" @3319' w/100 Sx.



Data Inc.

|                |            |  |
|----------------|------------|--|
| (KB Spl Tops.) |            | RID 3320, 4 1/2" @3319' w/100 Sx., CO Perf 16/ |
| Anh            | 623 /1246  | 3220-24, 40/3184-94, 12/3152-55, 4/3102-03     |
| RID            | 3320 -1451 | (Kc) 500 Reg A x 4000 gell-x 100 Acid, WI      |
| (Sj Iops.)     |            | Well in Kc, No Input tests - COMPLETED 5-4-    |
| Hb             | 2882 -1013 | 65   |
| BL             | 2990 -1121 |  |
| Kc             | 3006 -1137 |  |
| Arb            | 3275 -1406 |  |
| LTD            | 3320 -1451 |  |

MAOIGEN