

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00717-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 15-15S-17W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: DEGENHART Well #: 1
County: ELLIS Total Vertical Depth: 3556 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3546
SURF Size: 8.625 feet: 218

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2004 12:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 600# hulls.
Fluids at 580'. Dakota 297'-697'. Anhy 1112'-1152'. Salt 1482'-1752'.
Perfs at 725' - 1140' - 1800'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2004 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Log Tech perfed well at 725' - 1140' - 1800'.
Poe Well Service RIH with tubing to 2000'.
Allied tied onto tubing and pumped 150 sxs 60/40 pozmix with 400# hulls to circulate cement to surface.
Pulled tubing - tied onto 5 1/2" casing and pumped 60 sxs cement with 200# hulls mixed in.
Max. P.S.I. 1200#. S.I.P. 900#.
Tied onto backside.
Max. P.S.I. 1000#. S.I.P. 1000#.

RECEIVED
JUL 20 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #10424.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

JUL 16 2004

LEBEN DRILLING, INC

#1 DEGENHART

15-15-17W
SW NW SE

Contr.

ELLIS County

E 1977RB Comm.

8-6-58

Comp. 10-10-58

IP

111 BOPD

PHY POT

ARB

Tops	Depth	Datum
ANH	1112	865
HEEB	3212	-1235
TOR	3232	-1255
LANS	3259	-1282
B/KC	3481	-1504
CHRTY CONG	3515	-1538
ARB	3545	-1568
TD	3556	-1575

Casing
 8" 218
 5" 3546
 DST 3320-40/1 HR, 10' 0 SPK M,
 BHP 0#
 DST 3400-40/1½ HR, 314' M,
 BHP 0#
 DST 3546-52/1 HR, 426' G, 100'
 CL 0, 115' M & GCO, BHP 1020#
 CO: SWB 3 BOPH, NATL: ACID 500
 SWB 11¼ BOPH/12 HR, NW
 DEGENHART POOL

+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS