


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rawlins County. Sec. 29 Twp. 2S Rge. 33 (E) W (W)  
Location as "NE/CNW4SW4" or footage from lines C/NW SW  
Lease Owner Edwin Foster Blair & Associates - Murfin Drilling Co.  
Lease Name HORINEK Well No. 1  
Office Address 617 Union Center Building - Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1/5/61 19  
Application for plugging filed 1/7/61 19  
Application for plugging approved 1/8/61 19  
Plugging commenced 1/8/61 19  
Plugging completed 1/8/61 19  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4536' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	130'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug 400', mixed and displaced 20 sacks through drill pipe.  
Set plug 125', mixed and displaced 20 sacks through drill pipe.  
Set plug 40', mixed 10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 9 1961

CONSERVATION DIVISION  
Wichita, Kansas

2-9-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company  
Address 617 Union Center Bldg. - Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Murfin - Partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Murfin  
617 Union Center Bldg. - Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of February, 19 61

My commission expires June 14, 1964

Mary Jane Blume  
Notary Public.



15-153-30119-00-00


KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Edwin Foster Blair & Associates and  
Murfin Drilling Company  
FARM HORINEK NO. 1

SEC. 29 T. 2S R. 33W  
LOC. C/NW SW

TOTAL DEPTH 4536'  
COMM. 12/26/60 COMP. 1/5/61  
SHOT OR TREATED  
CONTRACTOR Murfin Drilling Company  
ISSUED

COUNTY Rawlins  
KANSAS



CASING  
20 10  
15 8 5/8" 130'  
12 6  
13 5

ELEVATION 2942' KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 50' Clay
- 60' Sand
- 1550' Shale
- 2250' Sand - Shale
- 2430' Shale with Sand Streaks
- 2435' Shale
- 2470' Gyp
- 2560' Shale and Gyp
- 2630' Red Bed
- 2740' Red Bed, Shale
- 2780' Anhydrite
- 2835' Shale
- 2960' Shale and Shells
- 3565' Shale - Lime
- 3745' Lime - Shale
- 4184' Lime
- 4255' Lime and Shale
- 4380' Lime
- 4450' Shale and Lime
- 4536' Lime - Shale

ELECTRIC LOG TOPS:

- Topeka 3759'
- Oread 3858'
- Lansing/Kansas City 3914'
- Base/Kansas City 4163'
- Cherokee Sand 4393'
- Mississippi 4508'
- Total Depth 4536'

DST #1 3830' - 3895' Open 2 hrs.  
Recovered 160' muddy salt water.  
IF 0# FF 0# BHP 860#/20 min.

DST #2 3930' - 3975' Open 1 hr.  
Recovered 1130' salt water. IF 0#  
FF 480# BHP 1250#/20 min.

RECEIVED  
STATE CORPORATION COMMISSIONER

FEB 9 1961

CONSERVATION DIVISION  
Wichita, Kansas

2-9-61