


15-153-20243-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Rawlins County, Sec. 4 Twp. 2S Rge. XXX33 (W)  
Location as "NE/CNW/SE/SW" or footage from lines C SE NW  
Lease Owner National Oil Company  
Lease Name Wolters Well No. 1  
Office Address 200 W. Douglas, Suite 550 Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed April 29 1976  
Application for plugging filed (Verbally) April 29 1976  
Application for plugging approved (Verbally) April 29 1976  
Plugging commenced April 29 1976  
Plugging completed April 29 1976  
Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4690  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	302'	K.B. None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug set @ 1200' with 70 sx.  
2nd plug set @ 300' with 20 sx.  
3rd plug set @ 40' with 10 sx.

Plug was down @ 4:30 p.m. April 29, 1976.  
STATE PLUGGER: Gilbert Balthazor

Name of Plugging Contractor Abercrombie Drilling, Inc. (If additional description is necessary, use BACK of this sheet)  
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.  
Jack K. Wharton-Geologist (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack K. Wharton  
801 Union Center, Wichita, KS 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May 1976

My commission expires July 21, 1979  
Margo Dee Montgomery Notary Public.



RECEIVED  
CONSERVATION DIVISION  
MAY 06 1976  
5-6-76  
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

OPERATOR: National Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: WOLTERS #1  
 LOCATION: C SE NW Section 4-2S-33W  
 Rawlins County, Kansas  
 SPUD DATE: April 21, 1976  
 COMPLETION DATE: April 29, 1976

0	227	Surface clay and sand
227	260	Sand & shale
260	1017	Shale
1017	1733	Shale & sand
1733	2224	Shale
2224	2575	Shale & sand
2575	2598	Chert
2598	2695	Shale & shells
2695	2870	Shale & shells
2870	2890	Shale
2890	2929	Anhydrite
2929	3468	Shale
3468	3619	Lime & shale
3619	3910	Shale & lime
3910	3930	Lime & shale
3930	4088	Shale & lime
4088	4140	Lime & shale
4140	4690	Lime
	4690	Rotary Total Depth

Drilled 305' of 12 1/4" hole. Ran 8 jts. of 8 5/8" casing. Set @302' K.B. (overall tally 296.29') Cemented with 185 sx. 50/50 Posmix, 3% ca.cl. Cement circulated, plug was down @ 12:30 a.m. April 21, 1976. Preparing to drill from under surface.

PLUGGED AND ABANDONED: 1st Plug was @ 1200' with 70 sx. cement. 2nd Plug was @ 300' with 20 sx. cement. 3rd Plug was @ 40' with 10 sx. cement. 50/50 Posmix, 6% gel. State Plugger: Gilbert Balthazor - Plug was down @ 4:30 p.m. April 29, 1976.

SAMPLE TOPS:	Anhydrite	2889' (+188)
	B/Anhydrite	2929' (+148)
	Lansing	4023 (-946)

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

NOTARY PUBLIC  
 MARGO DEE MONTGOMERY  
 WOLTERS, KANSAS  
 5-6-76

Jack K. Wharton, Geologist of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WOLTERS #1, C SE NW, Section 4-2S-33W, Rawlins County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jack K. Wharton  
 Jack K. Wharton, Geologist

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 5th day of May, 1976.

Margo Dee Montgomery  
 Margo Dee Montgomery, Notary Public

