

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Jason Oil Company

Address: P. O. Box 701, Russell, KS 67665-0701

Phone: (785) 483 - 4204 Operator License #: 6622

Type of Well: SWD Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 4-29-04 (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API Number: 15 - 053-19006-00-01

Lease Name: Harbacek

Well Number: 3

Spot Location (QQQQ): - NE - NW - NW

4950 Feet from North / XX South Section Line

990 Feet from East / XX West Section Line

Sec. 7 Twp. 16 S. R. 10 East XX West

County: Ellsworth

Date Well Completed:

Plugging Commenced: 4-29-04

Plugging Completed: 4-29-04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Ran sand line bailer to 1600' and pulled up cement. Perf. gun would not go below 980'; perforated at 980' and 410'; run tubing to 1400', pumped 30 sxs cement; pull tubing to 1000' and pump 50 sxs of cement with 100# of cotton hulls; pull tubing to 410' and circulate cement to surface.

All cement 60/40 posmix with 4% gel

Name of Plugging Contractor: Professional Pulling Services, LLC License #: 32810

Address: P. O. Box 486, Hays, KS 67601-0486

Name of Party Responsible for Plugging Fees: Jason Oil Company

State of Kansas County, Russell, ss.

James L. Schoenberger


(Employee or Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) James L. Schoenberger

(Address) P. O. Box 701, Russell, KS 67665-0701

SUBSCRIBED and SWORN TO before me this 14th day of July 2004

Fred Weigel, Jr. Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED JUL 19 2004 KCC WICHITA

Handwritten signature