

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: K & N Petroleum, Inc.
 Address: 513 West 6th Street, Ellinwood, Kansas 67526
 Phone: (620) 564-3422 Operator License #: 3208
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: June 21st, 2004 (Date)
 by: District 2 - No KCC agent on location (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: 3066' Bottom: 3338' T.D. 3343'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: ¹⁵⁹15-157-20,199-00-00
 Lease Name: Oberle
 Well Number: #1 - V ^{KCC Perm #11104}
 Spot Location (QQQQ): NW - NW - NW -
 _____ Feet from North / South Section Line
 _____ Feet from East / West Section Line
 Sec. 16 Twp. 19 S. R. 10 East West
 County: Rice
 Date Well Completed: 4/15/1969 ^{KCC Perm #11104}
 Plugging Commenced: 6/24/04
 Plugging Completed: 6/25/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	216'	8-5/8"	216'	0'
	Production	0'	3338'	5-1/2"	3338'	1565.03'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Brackeen spotted sand-35 bbls. total - let fall. Spotted cement on bottom. M.I.R.U. casing jacks. Pulled slips - pulled stretch. Worked a bit. Trip in hole with knife. Cut @1700' - won't pull. Cut @1550' - pulled to 1250'. Allied pumped 35 sx - 100# hulls. Pulled to 900' - pumped 35 sx - 100# hulls. Pulled to 290' - pumped 100 sx - circulated cellar full. Pulled rest of pipe. Tore down equipment and moved off.


Name of Plugging Contractor: D. S. & W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: K & N Petroleum, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

Edward S. Nemnich
(Signature)
P.O. Box 231, Claflin, Ks. 67525
(Address)

SUBSCRIBED and SWORN TO before me this 28th day of June, 20 04

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

B...

CONSERVATION DIVISION
WICHITA, KS

JUL 01 2004

RECEIVED
KANSAS CORPORATION COMMISSION

CONSERVATION DIVISION
WICHITA, KS

JUL 01 2004

RECEIVED
KANSAS CORPORATION COMMISSION

RECEIVED
CONSERVATION COMMISSION

JUN 22 2004

CONSERVATION DIVISION
WICHITA, KS